

# Status and High Power Performance of the 10 MW, 140 GHz ECH System for the Stellarator W7-X



18th International Toki Conference (ITC18)  
Development of Physics and Technology of Stellarators/Heliotrons  
en route to DEMO  
December 9-12, 2008 Ceratopia Toki, Toki Gifu JAPAN



**M. Thumm<sup>1</sup>, G. Gantenbein, S. Illy, S. Kern, B. Piosczyk, M. Schmid**

*Forschungszentrum Karlsruhe, Association EURATOM-FZK, Institut für Hochleistungsimpuls- und Mikrowellentechnik (IHM),  
Postfach 3640, D-76021 Karlsruhe, Germany,   <sup>1</sup>and Universität Karlsruhe, IHE, D-76131 Karlsruhe, Germany*

**H. Braune, V. Erckmann, H.P. Laqua, N.B. Marushchenko, G. Michel, Y. Turkin, M. Weissgerber**

*Max-Planck-Institut für Plasmaphysik (IPP), Association EURATOM-IPP, Teilinstitut Greifswald, D-17491 Greifswald, Germany*

**P. Brand, W. Kasperek, C. Lechte**

*Universität Stuttgart, Institut für Plasmaforschung (IPF), D-70569 Stuttgart, Germany*

**and the W7-X ECH Teams at FZK Karlsruhe, IPP Greifswald and IPF Stuttgart**

## Heating and Current Drive:

- *Modes of operation*
- *Steady state scenarios*

## The ECH & CD Plant:

- *Gyrotrons*
- *Transmission lines*
- *In-vessel components*

## Gyrotron Technology Improvement:

- *TFSS at gyrotron collector*

# ECH & CD for W7-X and for ITER

## “Day one“ Heating & Current Drive Systems

	W7-X	ITER
Installed Power (MW)	10	27 (incl. Start-up assist)
Power/Gyrotron (MW)	1	1 (EU: 2)
Frequency (GHz)	140	170
Mode of Operation	2 <sup>nd</sup> Harm. (2.5 T) CW (1800 s)	1 <sup>st</sup> Harm. (5.4 T) CW (1000 s)
Transmission System	Optical	Waveguide
Type of Launchers	Front steering/Remote steering	Front steering
Physics Demands	Plasma start up	Start-up assist
	Bulk heating and current drive	Bulk heating and current drive
	q-profile shaping	q-profile shaping
		MHD control
	Net-current suppression	Net-current enhancement

# ECH & CD: Operation Scenarios for W7-X

## Plasma Density Range

**Cyclotron Frequency:**

$$\omega_c = \frac{eB}{m}$$

determines the microwave frequency:



$$\omega - n\omega_c / \gamma - k_{||}v_{||} = 0 \quad \gamma = 1 / \sqrt{1 - \frac{v^2}{c^2}}$$

(2.5 T, n = 2, 140 GHz for W7-X)

**Plasma Frequency:**

$$\omega_p^2 = \frac{e^2 n_e}{\epsilon_0 m_e}$$




determines the density range



# ECH: Predicted Plasma Parameters for W7-X (I)


3rd harmonic X-mode, 140 GHz,  $B_{\text{res}} = 1.67 \text{ T}$ ,  $n_{e,\text{crit}} = 1.6 \cdot 10^{20} \text{ m}^{-3}$

- \* Operation at reduced B-field, optically grey
- \* Toroidal launching angle similar to O2-mode at 140 GHz (12.3 deg.)




# ECH: Predicted Plasma Parameters for W7-X (II)

2nd harmonic O-mode, 140 GHz, 2.5 T






$n_e = 1.8 \cdot 10^{20} \text{ m}^{-3}$ ,  $T_e = 2.6 \text{ keV}$



N. Marushchenko, et al., 2007


Transition of 2nd harmonic X-mode to 2nd harmonic O-mode  
 - assume neoclassical core confinement with ‘anomalous edge’ -




- ✿ Plasma start - up and heating with X2 (5 MW) Y. Turkin, et al., EPS, 2007
- ✿ Tuning launching angle (12 deg.) and polarization towards O2
- ✿ Increase plasma density
- ✿ Increase ECH power (10 MW) and plasma density

# ECH & CD: Predicted Plasma Parameters for W7-X

## Steady state operation: Current control by ECCD



- \* ECCD for bootstrap current compensation  
 $I_{BS} = 7\text{kA} \rightarrow 22\text{kA}$
- \* Adjust power in P1
- \* Drive current with P2 (launching angle)
- \* Control edge rotational transform





Y. Turkin et al. FS&T 2006

N. Marushchenko, SMSA 2007

# ECH & CD: Features Beyond Specifications

## 2nd frequency at half power: 103.8 GHz



- ★ Gyrotron diamond window transparent at  $d = 4\lambda/2$  (140 GHz) ... also at  $3\lambda/2$  (105 GHz)
- ★ Two cavity modes can be exited : TE<sub>21,6</sub> (**103.8 GHz**) and TE<sub>22,6</sub> (**106.3 GHz**)
- ★ However reduced efficiency : 21 - 27 %
- ★ RF power limited by collector (<1.3 MW)




# ECH: Predicted Plasma Parameters for W7-X

2nd harmonic O-mode, 103.8 GHz,  $B_{\text{res}} = 1.85 \text{ T}$ ,  $n_{e,\text{crit}} = 1.4 \cdot 10^{20} \text{ m}^{-3}$

- \* Operation at reduced B-field, optically grey, reduced power < 4 MW
- \* Toroidal launching angle similar to O2-mode at 140 GHz, 3 - pass absorption




# ECH & CD System for W7-X: Schematic



**HV-Modules (IPF):**  
10 delivered and operational

**Single-Beam Section Optics (IPF):**  
Full performance test completed

**Multi-Beam Section Optics (IPF):**  
First full performance test (with single beam) completed



2 rows of gyrotrons with water cooling modules

Spare boxes for future upgrade

# ECH & CD Supporting Systems: HV- Supply and Water- Cooling Plant



## HV Modulator: IPF Design (tetrode based)

- ★ + 30 kV, 0.5 A supply (energy recovery)
- ★ Fast regulator/modulator  
(20 kHz demonstrated)
- ★ Thyratron crowbar,  
HV-control system
- ★ All 10 units completed  
and operational




- ★ Gyrotron cooling modules (< 20 MW)
- ★ Central mirror cooling module (< 0.7 MW)
- ★ Launcher- and dummy load cooling (< 2 MW)
- ★ All units completed and operational

## Gyrotrons...



- ★ 8 out of 10 gyrotrons delivered and tested,
- ★ # 2 (2a), #3 (3a), #4 failed to meet the specs, beam tunnel problem (new atten. ceramics) , parasitic oscillations
- ★ #5 presently under test, shifted output beam!


## ....and the quasi-optical transmission system Single-Beam Module      Multi-Beam Section



- ★ Transmission lines in the beam duct completed (except BMO)
- ★ Most loaded section tested at full performance (920 kW/ 30 min)
- ★ Retro-reflectors installed, first integrated tests of the “full-distance transmission”

# Integrated CW-Tests with TED- and CPI- Gyrotrons

- Reliable 30 min operation achieved (here 5 min + 30 min shots)
- All temperature sensors in the gyrotron and transmission line mirrors stationary




Gyrotron output power > 0.92 MW (TED)  
> 0.90 MW (CPI)

After transmission through 7 mirrors:

Power in Gaussian mode 0.87 MW (TED)  
0.83 MW (CPI)

(estimated losses are 50 - 70 kW, imperfect  
BMO, improvement under way)

## Thermographic Image of the Output Beam (0.95 MW)



**Analysis of measurements with PVC target at several positions**

**Beam parameters:**

**Waist:** 18.1 / 18.5 mm

**Waist position:** 105 / 51 mm

**Gaussian content:** ~ 97 %

**Mode purity of all gyrotrons > 95 %**



# Gyrotrons, Magnets and Loads: Status



- ★ TED Maquette operational
- ★ TED Prototype operational
- ★ TED #1 operational, "mothballed"
- ★ TED #5 full performance 0.92 MW, 30 min
- ★ TED #4, 3a, 2a presently under test at FZK  
parasitic modes in beam tunnel  
at TED for repair
  
- ★ CPI Prototype full performance 0.9 MW, 30 min,  
presently under re-test at IPP  
after a vacuum-leak repair
  
- ★ All SC-Magnets and PS's delivered and operational


★ Dummy Loads: TED load at FZK teststand has water leak (fatigue)  
CCR loads at IPP have reduced performance (< 0.75 MW, CW)  
now operated in tandem configuration

# ECH: Near-Torus Transmission: The ECH&CD Towers




- ✿ House of optical elements to distribute and match the RF beams to the 'equatorial-plane' and 'HFS'-launchers
- ✿ Heavy granite structure is good mm-wave absorber
- ✿ "Towers" completed, presently installation of optical elements, remote control system, cooling etc.

## Quasi-Optical Transmission, Beam Path



**Single-Beam Module**




**Beam-Combining Optics  
MBWG and CW Load**



- ★ **Transmission lines in the beam duct completed (except BMO)**
- ★ **Most loaded section tested at full performance (920 kW/ 30 min)**
- ★ **Retro-reflectors installed, first high power tests of “full-distance transmission”**

# ECH & CD: Long Distance Transmission

## High Power Measurements on MBWG



- \* Wave beam is transmitted half way to the torus and then reflected by retro-reflector (40 m)
- \* 10 mirrors
- \* Beam power measured calorimetrically
- \* Measured losses are 2.7 %, agree with theoretical losses

ITEM	OHMIC (%)	DIFFR. (%)	(%)
M5, M6, M7	0.39	0.2	0.59
2 SR	0.26	0.1	0.36
M5, M6, M7	0.39	0.2	0.59
M4	0.13	0.1	0.23
SD	0.13	0.1	0.23
ATMOSPH.	0.68		0.68
SUM			2.68 %
MEASURED			2.7 + 0.4%

# W7-X: The In-Vessel Transmission System Plug-In Front Steering Launchers




- ★ Combines 3 RF beams per port with wide steering range (O2, X3, O-X-B, ECCD): toroidal  $< 35^\circ$ , poloidal  $< 30^\circ$
- ★ Simplified launcher mock-up tested, concept for in-vessel driving rods and mirror cooling qualified
- ★ Survived 10 000 load cycles
- ★ Tested in MISTRAL facility (mm-wave stray-radiation loading).
- ★ Fabrication/assembly of all 4 launchers in progress


# W7-X: In-Vessel Transmission and Diagnostic

## Inner Vacuum Vessel Wall, TZM Reflector

TZM: Titanium- Zirconium- Molybdenum



- \* TZM tiles for in-vessel reflection qualified with 0.5 MW incident power
- \* Thermal loading acceptable with polished surface ( $T_{surf} < 470 \text{ }^{\circ}\text{C}$  in CW)





*Good knowledge of beam location on TZM tiles required*

- \* ECA diagnostics and beam position control
- \* Measure non-absorbed power
- \* Pick-up horn antenna array (120 horns)
- \* Routing of WGs in progress

# W7-X: In-vessel ECA- Diagnostic Routing of Pick- Up Waveguides to TZM Reflectors



- ★ Pick- up horn antenna array (120 horns)
- ★ Routing of circular WGs towards ports
- ★ Prototype under fabrication, tests soon



# Advanced Transverse Field Sweeping System (TFSS)

50 Hz rotating perturbative field  
...with small VF-modulation (VFSS)

(V.Erckmann, G. Dammertz, M. Schmid., Patent 2007)



- ★ TFSS only does not solve the problem completely!  
→ Combination of conventional VFSS and novel TFSS
- ★ Obtain smooth distribution, increase collector capability (factor of 2)
- ★ Modulated TFSS satisfies the demands for next-step gyrotrons

- ★ The project has arrived an advanced state, all major systems are completed and running, presently ECH work concentrates on near-torus and in-vessel components (N-port, ECA)
- ★ The series production of gyrotrons still needs close attention. Investigation of different beam tunnel geometries up to mid 2009. SN7 (#10) is expected beginning of 2011.
- ★ Extended operation regime: Promising perspective for 2-frequency operation 140 GHz and 103.8 GHz (at half power)
- ★ Steady state scenarios under investigation
- ★ First high-power measurements on long distance transmission:  
**losses are very low (2.7 %) and agree with theoretical losses**
- ★ Development and test of advanced gyrotron components
  - Improved gyrotron collector sweeping