

# Steady-State In Vessel Components for the Wendelstein 7-X Stellarator

Reinhold J. Stadler

Max-Planck Institute for Plasma  
Physics Greifswald, Germany  
on behalf of the W7-X Team




- I. Overview**
- II. Divertor Components**
- III. Wall Protection Components**
- IV. Component Testing**
- V. Component Assembly**
- VI. Conclusions**



## In-Vessel Components for steady-state Operation

### Main Features

- Surface 265 m<sup>2</sup>
- Mass approx. 33,8 tons
- 250 000 parts  
130 000 non-standard parts  
4000 different profiles
- 4.5 km internal cooling piping  
with about 900 branches



Location of in-vessel components,  
“Bean-shape” cross-section  
at 0° toroidal angle

### Two step approach requires intermediate components:

- Inertial cooled divertor (TDU) for first operation phase
- Actively cooled high-heat-flux (HHF) divertor for steady state phase




- I. Overview
- II. Divertor Components ←
- III. Wall Protection Components
- IV. Component Testing
- V. Component Assembly
- VI. Conclusions



## Test Divertor, inertial cooled for Commissioning


- 25m<sup>2</sup> TDU: solid graphite tiles
- Will be installed by 2014 for the first operation phase of W7-X
- Simple structure, installation, adjustment, diagnostic integration
- Same geometry as HHF divertor
- Ease of assembly and adjustment after machine start up to magnetic configuration of W7-X
- Purpose: development of discharge scenarios for high heat flux divertor  
⇒ optimized operation of high heat flux divertor



Test divertor (TDU)-target concept,  
with baffle-modules and toroidal  
divertor closure

## High-Heat-Flux Divertor, required for Steady-State Operation

- 10 divertor units installed up down symmetrically
- Divertor unit: set of horizontal and vertical target modules
- Target module: set of target elements



Prototype module with manifolds on adjustable frame


### Main characteristics:

|                        |                      |                     |
|------------------------|----------------------|---------------------|
|                        | 10 MW/m <sup>2</sup> | 1 MW/m <sup>2</sup> |
| Total area             | 19 m <sup>2</sup>    | 6 m <sup>2</sup>    |
| Target modules         | 100                  | 20                  |
| Target elements        | 890                  | 250                 |
| Plasma facing material | CFC                  | Graphite            |


## Fabrication: CFC NB31

- **3D-anisotropic material** with complex manufacturing process
- Planned fabrication: from 2001 to 2003 (delivered in 2006...)

| Thermal conductivity | Temperature [°C] | Minimum [W.m <sup>-1</sup> .K <sup>-1</sup> ] | Average [W.m <sup>-1</sup> .K <sup>-1</sup> ] |
|----------------------|------------------|---|---|
| Ex-pitch             | RT               | 260   | 300   |
|                      | 800              | 120   | 140   |
| Ex-PAN               | RT               | 100   | 110   |
|                      | 800              | 48  | 55  |
| Needling             | RT               | 85  | 100   |
|                      | 800              | 40  | 45  |



| Tensile strength [MPa] | Minimum |
|------------------------|---------|
| Ex-pitch               | 110     |
| Ex-PAN                 | 20      |
| Needling               | 5       |



- Scattering of tensile strength in the ex-pitch fibre direction between delivered batches
- Around 900 kg available for pre-series and serial productions of target elements

➤ [Additional qualification steps](#)

## Target Elements for steady-state Operation: Design

### Thermal performances:


- Max. stationary heat flux 10 MW/m<sup>2</sup>
- Max. power per element 100 kW

### Technology:


- Heat sink CuCrZr
- Plasma facing material CFC NB31
- Interlayer CFC-heat sink bi-layer\*  
(\* = AMC® tiles with HIP OFHC-Cu)
- Joining CFC-heat sink EBW
- Cooling swirl tapes

### Water-cooling characteristics:

- Max. inlet/outlet temp 30°C / 80°C
- Static pressure 1 MPa
- Velocity 8-10 m/s



890 elements - 13 types  
250 ≤ length ≤ 595 mm




Cross-section





## Target Elements for steady-state Operation: Fabrication

- ~900 elements, 13 types, ~18000 CFC tiles
- Pre-series achievements: bi-layer, improved heat sink
- Original launching of serial fabrication: 2004 (not started...)



[Inspections between steps are not shown]



Heat sink

## Target Elements for steady-state Operation: Pre-series phase

- Planning: ~1 year from end 2003 to end 2004 (not completed in 2008...)
- Pre-series 1, 2, 3, 4 = ~ 60 full-scale elements manufactured: 100% HHF tests in GLADIS

### Extended pre-series activities:

- To minimize risks for serial fabrication
- To guarantee W7-X HHF divertor operation
- Boundaries: planning, budget, manpower, contractual matters

### Results of the last pre-series test campaign (2008):

- 100% accepted: 10 elements or 100 tiles (100 cycles @ 10 MW/m<sup>2</sup>, 10s) without failure
- Extended cycling: up to 10 000 cycles @ 10 MW/m<sup>2</sup>, 10s with no visible cracks (1 element)
- Simulation of transient overloading: 1000 cycles at 20 MW/m<sup>2</sup>, 3s without failure
- Extended heat flux: 24 MW/m<sup>2</sup> (15 MW/m<sup>2</sup> design), close to interface melting temperature
- Critical heat flux: 31 MW/m<sup>2</sup> (25 MW/m<sup>2</sup> specified), without armor


### Conclusion:

- The bonding technology between CFC tiles and CuCrZr heat sink is qualified
- Further development and verification of the cooling structure and end-tile design required


## Actively cooled Baffle Module and Toroidal Divertor Closure

### Baffle Module:


- Graphite-tiles clamped to CuCrZr-cooling structures onto which stainless steel cooling meander is brazed
- Peak steady state heat flux 500 kW/m<sup>2</sup>
- 170 baffle modules, 50 manufactured



Baffle module with  
graphite tiles



Cooling structure



### Toroidal Divertor Closure:


- 10 modules
- Baffle-type technology
- Concept available

## Cryo Vacuum Pump with Cryo-Feed-Through

Design based on ASDEX Upgrade – cryo vacuum pump

### 10 identical pumps:

- Effective length 11,8 m
- 2 units DCU1 and DCU2, connected in line
- Shielding against plasma radiation via water cooled chevrons




About 80% of parts manufactured - **Only installed for second phase operation**



## Control Coils with Current-Connectors

- 10 Control coils, located behind baffles, manufactured by BNG, water-cooled
- 8 turns hollow Cu-conductor, allows to sweep target point by  $\pm 1-2$  cm and to correct minor error fields.
- Electrical current 2,5 kA DC, 625 A AC at between 1 -20 Hz.



All coils are delivered, tested and accepted




Control coil in test facility at IPP

- I. Overview
- II. Divertor Components
- III. **Wall Protection Components** ←
- IV. Component Testing
- V. Component Assembly
- VI. Conclusions



## Wall Protection for steady-state Operation: Heat Shields, Housings, Panels and Port liner



### Heat Shields and Diagnostic Housings:


- Same technology as baffle modules
- Peak steady state heat flux  $300 \text{ kW/m}^2$
- Actively cooled
- 162 heat shields required, 101 manufactured



## Panel Elements in thermally low loaded Areas

### Panels, Poloidal Divertor Closure and Pumping Gap Panels :


- Manufactured at MAN-DWE
- Peak steady state heat flux  $200 \text{ kW/m}^2$
- Quilted steel panels
- Actively cooled
- 320 panels, 200 delivered to date



Panels installed in 1:1 wooden  
mock up of plasma vessel (top)  
Panel, view from the rear (left)



## Plug-Ins and Cooling Circuits



Cooling circuit prototype,  
installed in 1:1  
wooden mock-up of  
the plasma vessel

### Cooling Circuits:

- 170 cooling circuits in 70 variants and versions
- Ca. 4,5 km pipe work in plasma vessel
- 900 branches
- 1500 components to be supplied, approx. 1500 interfaces and 3800 joints
- The first components are manufactured

### Prototype plug-in

### Plug-Ins:

- 80 plug-ins, 8 variants and several versions
- Up to 9 feed-throughs per plug-ins
- Some with diagnostic cabling



- I. Overview
- II. Divertor Components
- III. Wall Protection Components
- IV. **Component Testing**
- V. Component Assembly
- VI. Conclusions




## Component Testing at ZTE (Workshop of IPP Garching)

### Vacuum chamber for hot leak tests:

- Diameter 1,2 m, length 3 m
- Integral leak tests from room temperature to 160 °C
- Cold leak tests at LN2-temperature
- Used for all in-vessel components
  - Targets
  - Control coils
  - Baffles
  - Heat shields, panels

### Others:

- Electrical test stand for control coils
- Hydraulic test facility
- 1:1 wooden mock up of plasma vessel segment






Vacuum chamber



## GLADIS, HHF-testing at IPP-Garching (Material Research Department)

### GLADIS facility:

- Max. ion beam power 1,4 MW
- Heat flux density 52 MW/m<sup>2</sup>
- Pulse duration 0.1 – 15 s
- Use for W7-X HHF-Tests on:
  - Target elements during development, definition of acceptance criteria, envisaged for serial acceptance tests
  - Panels to verify un-cooled operation





- I. Overview
- II. Divertor Components
- III. Wall Protection Components
- IV. Component Testing
- V. **Component Assembly**
- VI. Conclusions



## General Strategy:

- In-vessel components are installed in parallel to other machine assembly
- Verification of assembly technology, assembly procedures, metrology and training is carried out with prototypes, real components in mock-ups and real plasma vessel segments
- Installation of components that are replaced for steady state operation
  - Install inertially cooled test divertor for commissioning phase  
(for steady state operation an actively cooled high heat flux divertor will be installed together with the cryo vacuum pump)
- Installation of components that are removed during preparation for steady state operation
  - Installed - but not connected to the cooling system – baffles
- Install all other components that are required for steady state operation, some of which must be cooled even in the commissioning phase
  - Cooling supply for wall protection
  - Wall protection
  - Control coils

## Assembly Strategy:

- Assembly of wall protection components in the plasma vessel is parallel to other activities in torus hall and connection of the machine modules
- For this a well developed assembly and logistics strategy is required
- Interaction with diagnostics, particularly for cabling and routing, as well as heating systems needs to be well defined
- Assembly of in-vessel components should be kept off the critical path
- Divertor components and wall protection tiles will be installed in the final phase in order to minimize the risk of damage

- I. Overview**
- II. Divertor Components**
- III. Wall Protection Components**
- IV. Component Testing**
- V. Component Assembly**
- VI. Conclusions**





## In-Vessel components for W7-X:

- All components designed for **steady-state operation at 10 MW**
  - actively cooled
- Design and production of the In-Vessel components for phased operation of W7-X shows **significant progress**.
- The **Test Divertor Unit** design is well advanced, test module in work.
- Geometrical and hydraulic layout of the **high heat flux targets** is tested with a prototype module.
  - Extensive high heat flux testing has verified the technology of the standard **target elements**.

## In-Vessel components for W7-X:

- All **control coils** are available.
- 80% of the parts for the **cryo vacuum pumps** are manufactured.
- 30% of **baffle modules** and 60% of **heat shield** structures are assembled. Procurement of graphite tiles for both components is running.
- Approximately 60% of the **wall panels** are delivered by MAN-DWE.
- Prototypes of **cooling circuits** and **plug-ins** have been successfully built and tested. Serial production of the cooling circuits has started.

## In-Vessel components for W7-X:

Delivery of components to IPP Greifswald has started.

The In-Vessel Component activities must continue at a high level over the next years to meet the machine assembly program.

